## FLOW RATING ANALYSIS FOR PUMP STATION S200



By Sheng Yue & Emile Damisse

April 2012

### SFWMD-HIST-026

Hydro Data Management Section Operation & Infrastructure Bureau South Florida Water Management District



FLOW RATING ANALYSIS FOR PUMP STATION S200

# **TABLE OF CONTENTS**

TABLE OF CONTENTS
LIST OF FIGURESII
LIST OF TABLES
ACKNOWLEDGEMENT
DEFINITIONSIV
EXECUTIVE SUMMARY1
1.0 INTRODUCTION
1.1       BACKGROUND
2.0 STATION DESIGN
2.1 PUMP PERFORMANCE TEST
3.0 STREAM FLOW DATA
4.0 RATING ANALYSIS
5.0 CONCLUDING REMARKS
REFERENCES10
APPENDIX A10
APPENDIX B
APPENDIX C10



#### FLOW RATING ANALYSIS FOR PUMP STATION S200

# LIST OF FIGURES

FIGURE 1. LOCATION MAP FOR PUMP STATION S200	2
FIGURE 2. PLAN VIEW OF PUMP STATION S200	3
Figure 3. profile view of \$200	4
FIGURE 4. COMPARISON BETWEEN MEASURED FLOWS AND DEVELOPED RATING	7
FIGURE 5. FLOW RATING CURVE FOR S200	9

# LIST OF TABLES

TABLE 1. DESCRIPTION FOR PUMP STATION S200	.4
TABLE 2. TSH AND DISCHARGE RELATIONSHIP	.5
TABLE 3. SUMMARY OF FLOW MEASUREMENTS	.6
TABLE 4. INITIAL COMPARISON BETWEEN MEASURED AND COMPUTED FLOWS	.7
TABLE 5. TSH AND DISCHARGE FROM SHIFTED RATING CURVE	.8
TABLE 6. FLOW RATING COEFFICIENTS FOR PUMP STATION S200	.8
TABLE 7. COMPARISON BETWEEN MEASURED AND COMPUTED FLOWS	.9



FLOW RATING ANALYSIS FOR PUMP STATION S200

# ACKNOWLEDGEMENT

The authors wish to express their appreciation to Jorge Jaramillo and Chris Bauer for collecting the pump performance curve and pump design information for this rating analysis.



FLOW RATING ANALYSIS FOR PUMP STATION S200

# DEFINITIONS

### Acronyms

AARE	Average absolute relative error
ARE	Absolute relative error
HW	Head water
TW	Tail water
SFWMD	South Florida Water Management District
TDH	Total dynamic head
TSH	Total static head



FLOW RATING ANALYSIS FOR PUMP STATION S200

## **EXECUTIVE SUMMARY**

Pump Station S200 consists of three identical electric pumps each with capacity of 75 cfs. This report summarizes a flow rating analysis for the pumps at Pump Station S200 based on the TSH vs. discharge relationship obtained from the pump performance tests with the calibration using the two flow measurements. The developed rating equation will be used to compute flow through the pump station.



South Florida Water Management District FLOW RATING ANALYSIS FOR PUMP STATION S200

## 1.0 INTRODUCTION

### 1.1 Background

Pump Station S200 is one of key components of the northern section of the C-111 Spreader Canal Phase 1 Project, which is located in southern Miami-Dade County in an area bounded by Everglades National Park, the Florida City-Homestead area, and Manatee. The main north portion of the project includes the Frog Pond Detention Area (FPDA), the Frog Pond Header Distribution Channel, and Pump Station S200.

The primary purpose of Pump Station S200 is to re-direct to the west up to 225 cfs of excess water from C111 Canal into FPDA. Pump Station S200 with design capacity of 225 cfs is located downstream of the existing S-176 structure, north of Ingraham Highway and west of the C-111 Canal along the northern boundary of the FPDA. **Figure 1** shows the location of the pump station.



**Fig 1.** Location of Pump Station S200

### **1.2** Objectives and Scope

We will conduct a rating analysis to develop a flow rating equation for Pump Station S200 to compute flow through the pump station.



FLOW RATING ANALYSIS FOR PUMP STATION S200

# 2.0 STATION DESIGN

Pump Station S200 houses three identical electric pumps with pump serial number SN10021, SN10022, and SN10023, each with capacity of 75 cfs. **Figure 2** illustrates the plan view of the pump station, and **Figure 3** the profile view of the pump station. **Table 1** provides description of the pump station.



Figure 2. Plan view of Pump Station S200



#### FLOW RATING ANALYSIS FOR PUMP STATION S200



Figure 3. Profile view of Pump Station S200

* *					
ITEM	Description				
Number of pumps	3				
Design pump capacity	75 cfs				
Engine motor horsepower	200 Hp				
Design engine speed	588 rpm				
Pump impeller speed	588 rpm				
Propeller Diameter	30 in				
Discharge pipe diameter	42 in				

Table	1.	Descri	otion	for	Pump	Station	S200
abic	т.	DUSCII	puon	101	1 ump	Station	

### 2.1. Pump Performance Test

The manufacturer conducted pump performance tests on these three pumps. The total dynamic head (TDH) computations of these pumps are given in Appendix A through C (MWI Corporation, 2011). **Table 2** below presents the total static head (TSH) versus discharge values which were extracted from Appendix A through C.



#### FLOW RATING ANALYSIS FOR PUMP STATION S200

Pump Serial No	Test Point	Pressure gauge height (in)	Static pressure (psi)	TSH (ft)	Flow (gpm)	Flow (cfs)
	1	26	6.35	16.82	32465	72.33
	2	26	5.00	13.70	34194	76.19
	3	26	4.10	11.63	35378	78.82
SN 10021	4	26	3.00	9.09	36297	80.87
	5	26	2.00	6.78	37193	82.87
	6	26	1.15	4.82	38068	84.82
	7	26	0.00	2.17	39345	87.66
	1	27	5.80	15.63	32465	72.33
	2	27	4.90	13.55	34194	76.19
	3	27	3.90	11.25	35378	78.82
SN10022	4	27	3.00	9.17	36297	80.87
	5	27	2.00	6.86	37193	82.87
	6	27	1.00	4.56	38068	84.82
	7	27	0.00	2.25	39345	87.66
	1	27	6.00	16.09	32210	71.77
	2	27	5.00	13.79	33952	75.65
	3	27	4.00	11.48	34909	77.78
SN10023	4	27	3.10	9.40	36069	80.36
	5	27	2.00	6.86	37414	83.36
	6	27	1.10	4.79	38284	85.30
	7	27	0.00	2.25	38924	86.73

Table 2. Initial TSH and Discharge Relationship

## 3.0 STREAM FLOW DATA

We conducted streamgauging at Pump Station S200 using Acoustic Doppler Current Profiler (ADCP) on February 23, 2012, and at Pump Station S199 on March 7, 2012. We can borrow the measured flow at S199 to calibrate the flow rating for S200 since the two stations have identical pump station design and identical pumps. **Table 3** summarizes the flow measurement, including the HW and TW stage, number of pumps in operation, engine speed, average discharge, and measurement quality tag. The quality of each flow measurement has been evaluated and assigned quality tag or qualitative accuracy qualifier by our stream gauging staff. There are six categories of qualifiers are used: "excellent (E)", "good (G)", "fair (F)", "poor (P)", "bad (B)", and "Not processed (N).



Date	HW Stage (ft, NGVD)	TW Stage (ft, NGVD)	# of Units	Avg Engine Speed (rpm)	Avg Discharge (cfs)	Device	Quality Tag
2/23/2012	3.01	8.70	3	588	225.56	ADCP	G
3/7/2012	2.26	7.80	2	588	224.48	ADCP	G

 Table 3. Summary of Flow Measurements

### 4.0 RATING ANALYSIS

We will develop a Case 8 flow rating equation for Pump Station S200 based on the TSH vs. discharge relationship obtained from the pump performance tests. Case 8 rating equation is developed by dimensional analysis and the pump affinity laws. Case 8 rating is the conventional rating equation representing all the possible cases, as documented in Damisse (2001) and Imru and Wang (2003). Equation below shows the Case 8 flow rating equation.

$$Q = A \left(\frac{N}{No}\right) + BH^{c} \left(\frac{No}{N}\right)^{2C-1}$$
(1)

$$H = \max\{CL, TW\} - HW \tag{2}$$

Where

Q:	Discharge in cfs;
<i>H</i> :	Total static head (TSH);
<i>N</i> :	Pump engine speed in rpm;
No:	Design pump engine speed in rpm (= 588 rpm);
<i>A</i> , <i>B</i> and <i>C</i> :	Regression coefficients determined through regression analysis (A > 0, B < 0, and C >
	1.0).
CL:	Discharge pipe outlet centerline elevation;
TW:	Tailwater elevation;
HW:	Headwater elevation.

For an electric pump with constant speed,  $N = N_o$ , and Equation (1) becomes

$$Q = A + BH^{C}$$
(3)

We conducted rating analysis by nonlinear regression analysis based on TSH vs. discharge values in **Table 2**. Figure 4 shows comparison of computed flows against tested data and measured flows. It



### FLOW RATING ANALYSIS FOR PUMP STATION S200

illustrates that the developed rating curve fits the tested data well, but is far away from the measured flows. **Table 4** lists the AARE between measured and computed flows and AARE is 12.5%. This indicates that given a TSH, the rating might overestimate flow through the pump station by 12.5%. Hence, the developed rating based on the tested data cannot represent real flow capacity of the pumps.



Figure 4. Comparison between measured flows and developed rating

Date	HW Stage (ft, NGVD)	TW Stage (ft, NGVD)	Avg Discharge (cfs)	Computed Flow (cfs)	ARE (%)
2/23/2012	3.01	8.70	75.2	84.3	12.1
3/7/2012	2.26	7.80	74.8	84.4	12.8
	12.5				

Table 4. Initial Comparison between Measured and Computed Flows

Each of the three pumps at Pump Station S200 has design capacity of 75 cfs. Our measured flow rates were close to the design capacity of the pump when all three pumps were running. Quality of the flow measurements are good and reliable based on our engineering judgment. The developed rating curve needs to be shifted near the measured flows. We shifted the developed rating curve using Eq. (1) by giving lower engine speed, i.e., N = 530 rpm and got the shifted curve which is in parallel with the original one. **Table 5 presents** TSH vs. discharge values from the shifted rating. We then conducted non-



#### FLOW RATING ANALYSIS FOR PUMP STATION S200

linear regression analysis on the shifted TSH vs. discharge values in **Table 5** to estimate rating coefficients in Equation (3). **Table 6** provides the flow rating equation coefficients of Eq. (3).

Total Static Head (ft)	Discharge (cfs)
0.0	79.660
0.5	79.456
1.0	79.157
1.5	78.808
2.0	78.422
3.0	77.563
4.0	76.613
5.0	75.588
6.0	74.500
7.0	73.356
8.0	72.161
9.0	70.922
10.0	69.640
11.0	68.319
12.0	66.962
13.0	65.571

### Table 5. TSH and Discharge from Shifted Rating Curve

 Table 6. Flow Rating Coefficients for the Pumps at S200

Rating Coefficient	Estimate	Approximate Lower 95% Confidence Limit	Approximate Upper 95% Confidence Limit
А	79.661	79.6601	79.661
В	-0.503	-0.5035	-0.5032
С	1.299	1.2989	1.2991

**Figure 5** illustrates the developed rating curve for the pumps at Pump Station S200. The diagram indicates that the rating curve from the developed rating equation well fits both the shifted data and measured flows. **Table 7** presents the relative errors between tested and calculated flows, and the AARE between tested and calculated flows is 0.4%. These results demonstrate that the developed rating can represent the relationship between total static head and discharge of the pump station.





Figure 5. Rating Curve for Pump Station S200

Table 7	Composicon	hotwoon	Maggunad	and	Computed	Flore
rable /.	Comparison	Detween	wieasureu	anu	Computed	<b>FIOWS</b>

Date	HW Stage (ft, NGVD)	TW Stage (ft, NGVD)	Avg Discharge (cfs)	Computed Flow (cfs)	ARE (%)
2/23/2012	3.10	8.70	75.2	74.8	0.5
3/7/2012	2.26	7.80	74.8	75.0	0.2
	0.4				

## 5.0 CONCLUDING REMARKS

We conducted rating analysis for Pump Station S200 based on the TSH vs. discharge relationship obtained from the pump performance tests. We then adjusted the rating based on the measured flows. **Table 6** presents the coefficients of the rating equation for Pump Station S200. The rating can be used to compute flow through Pump Station S200 for now. However, it needs to be further calibrated, and to be potentially improved based on more flow measurements in the future.



# REFERENCES

Damisse, E. 2001. Flow rating development for G335 Pump Station in STA-2. Hydrologic Data Management Division, South Florida Water Management District, West Palm Beach, Florida.

Imru, M. and Y. Wang. 2003. Flow Rating Analysis Procedures for Pumps. Technical Publication EMA # 413, South Florida Water Management District, West Palm Beach, Florida.

MWI Corporation, 2011. South Florida Water Management District S-199 & S-200 Pump Stations: Full Size Pump Performance Test, MWI JOB # 10021, Deerfield Beach, Florida.



FLOW RATING ANALYSIS FOR PUMP STATION S200

### Appendix A. SN 10021 TDH calculation

26	auge height	pressure g	mate		21-Jan-11	Test date Pump Model Description Pump Serial No	
326	rient (FLA)	or run ioad cu	mou		SEA330		
0.05	value (pipe)	friction K	e :		10021		
4.49	otor region)	value (for me	friction k	rpm	588	pump speed	Water
0.78	arge elbow)	friction k value (for discharge elbow)		inches	41.5	Fest pipe ID	
				Venturi	Static	pump	
		r into motor	electric powe	reading	Pressure	speed	Test
		(kWs)	(amps)	("H <sub>2</sub> 0)	(psi)	(mm)	Point
		177	338	32.0	6.35	(ipiii)	1
		169	326	35.5	5.0		2
		163	315	38.0	4.1		2
		155	305	40.0	3.0		3
		146	295	42.0	2.0		
		141	2.93	44.0	1.15		5
		128	271	47.0	0.0		7
		120	271	47.0	0.0		,
			disch elbow	motor region	pipe		
			friction	friction	pipe friction		
WHP	TDH	Flow	Hf	Hf	Hf	Hv	Vel
	(ft)	(gpm)	(ft)	(ft)	(ft)	(ft)	(ft/sec)
185.6	22.6	32465	0.72	4.13	0.05	0.92	7.70
174.0	20.2	34194	0.80	4.59	0.05	1.02	8.11
165.6	18.5	35378	0.85	4.91	0.05	1.09	8.39
150.0	16.4	36297	0.90	5.17	0.06	1.15	8.61
135.4	14.4	37193	0.94	5.43	0.06	1.21	8.82
123.2	12.8	38068	0.99	5.68	0.06	1.27	9.03
106.4	10.7	39345	1.05	6.07	0.07	1.35	9.33

### Appendix B. SN 10022 TDH calculation

Test date Pump Model Description Pump Serial No Water pump speed Test pipe ID		25-Jan-11 SEA330 10022 588 41.5	rpm inches	pressure gauge height motor full load current (FLA) friction k value (pipe) friction k value (for motor region) friction k value (for discharge elbow)			27 328 0.05 4.49 0.78	
		pump	Static	Venturi				
	Test	speed	Pressure	reading	electric pow-	er into motor		
	Point	(rpm)	(psi)	("H <sub>2</sub> 0)	(amps)	(kWs)		
-	1	(-1)	5.8	34.0	348	179		
	2		4.9	36.5	335	170		
	3		3.9	38.5	323	163		
	4		3.0	41.0	313	156		
	5		2.0	42.5	301	147		
	6		1.0	45.0	290	140		
	7		0.0	46.5	278	130		
pipe motor region disch elbow								
			pipe friction	a friction	friction		TDI	37110
	Vel	HV	HI (A)	HI (P)	HI (ft)	(mpm)	(ft)	WIIF
=	(fl/sec)	0.09	0.05	4 39	0.76	33464	21.8	184.3
	8.22	1.05	0.05	4.39	0.82	34672	20.2	176.8
	8.45	1.05	0.05	4.97	0.86	35610	18.2	164.1
	8 72	1.11	0.00	5 30	0.92	36748	16.6	154.3
	8.87	1.10	0.06	5.49	0.95	37414	14.6	137.9
	9.13	1.29	0.06	5.81	1.01	38498	12.7	123.9
	9.28	1.34	0.07	6.01	1.04	39135	10.7	105.8



### Appendix C. SN 10023 TDH calculation

\_\_\_\_\_

	Pump Model 1 Pum Water p T	Test date Description p Serial No pump speed Test pipe ID	24-Mar-11 SEA330 10023 588 41.5	rpm inches	moto friction k friction k va	pressure g or full load cu friction k v value (for mo lue (for disch	auge height rrent (FLA) /alue (pipe) otor region) arge elbow)	27 328 0.05 4.49 0.78	
	Test Point	pump speed (rpm)	Static Pressure (psi)	Venturi reading ("H <sub>2</sub> 0)	electric powe (amps)	r into motor (kWs)			
	1		6.0	31.5	330	174			
	2		5.0	35.0	321	168			
	3		4.0	37.0	316	162			
	4		3.1	39.5	306	156			
	5		2.0	42.5	279	133			
	6		1.1	44.5	269	125			
	7		0.0	46.0	267	122			
			nine	motor regio	u disch elbow				
			nine friction	friction	friction				
	Vel	Hv	Hf	Hf	Hf	Flow	TDH	WHP	
	(ft/sec)	(ft)	(ft)	(ft)	(ft)	(gpm)	(ft)		_
	7.64	0.91	0.05	4.07	0.71	32210	21.8	177.5	
1	8.05	1.01	0.05	4.52	0.79	33952	20.1	172.8	
	8.28	1.06	0.05	4.78	0.83	34909	18.2	160.5	
1	8.56	1.14	0.06	5.10	0.89	36069	16.6	151.1	
	8.87	1.22	0.06	5.49	0.95	37414	14.6	137.9	
	9.08	1.28	0.06	5.75	1.00	38284	12.9	124.5	
	9.23	1.32	0.07	5.94	1.03	38924	10.6	104.3	